MYSORE HEAD-QUARTER RANGE.

Dated 28th February 1920.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Head-quarter Range, Mysore, up to 20th March 1920, for the Improvement of the Southern Facade of the University Library at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1920.

2. The plans, detailed estimates and conditions may be seen at the Assistant Engineer's Office at Vanivilas Road, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (500) five hundred, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving the Southern Facade of the University Library at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable quantities for the Improvement of the Southern Facade of the (Jubilee Institute) present University Library.

No.	Items of work	Per	Adding rooms in the end halls	Adding verandah to the side halls	Adding rooms to the central portion	Steps in the center
1	Earthwork excavation and filling in	C. yd.	89	62	38	33
2	Concrete foundation	C. ft.	604	419	264	892
3	Do superstructure	„	2,896	176	1,011	..
4	Do arch work	„	..	..	36	..
5	Burnt stone slabs nicely dressed for steps ..	S. ft.	..	..	..	723
6	Do roughly dressed	„	270	..	128	..
7	Polished and rounded Kadapa or shahabad slabs ..	„	53	..	..	..
8	Plastering with chunam	Sqr.	43·42	..	16·04	..
9	Teakwood work wrought and put up	C. ft.	130·16	114·03	70·72	..
10	Pukka terrace	Sqr.	·42	10·58	4·92	..
11	Do excluding flat tiles	„	4·89	..	..	..
12	Roofing with Mangalore tiles on teak rafters ..	„	7·28	..	..	..
13	Ridging with Mangalore tiles with mortar ..	R. ft.	26	..	..	..
14	Teakwood ½″ planked ceiling	Sqr.	5·98	..	..	..
15	12″ cornice inside at roof level	R. ft.	114	..	..	..
16	12″ high basement moulding at bottom	„	108	84	..	..
17	6″ Do top	„	108	88	..	..
18	9″ moulding dentel below ventilators front ..	„	80	..	..	..
19	Corinthian pillars 1¾ diameter with bottom and capital, complete.	Each	8	..	..	..
20	Corinthian entablature with frieze 2′ projection, etc., complete.	R. ft.	138	..	65	..
21	Stone slabs for projecting the cornice	„	138	..	65	..
22	Balustrated parapet wall top and bottom cornice 4′ high.	„	41	52	58	..
23	Teakwood half panneled and half glazed windows framed hinges, etc., complete.	S. ft.	203	..	..	..
24	Teakwood glazed ventilators frame, hinges, bolts, etc.	„	74	..	..	..
25	Teakwood battend doors, frames, hinges, bolts, lock etc., complete.	„	44	..	..	..
26	Painting with silicate, 2 coats	Sqr.	8·05	..	..	..
27	Concrete floor for cellar room and plastering, etc. ..	„	3·27	..	..	..
28	Ornamental flower at the gabel end	Each	4	..	..	..
29	Highly enriched finials on top of pediments and enos	„	2	..	..	..
30	Chunam plastering to the basement with pointing ..	Sqr.	7·28	8·08	..	6·49
31	Wood oiling	„	10·00	9·85	6·00	..
32	Flooring with hexagonal Italian tiles and cement pointing, excluding concrete.	„	3·85	..	..	..

No.	Items of work	Per	Adding rooms in the end halls	Adding verandah to the side halls	Adding rooms to the central portion	Steps in the center
33	Rolled steel girders Railway freight, hoisting and painting, etc., complete.	Cwt.	10	22	10	..
34	White and colourwashing	Sqr.	50·70	8·00	16·04	6·40
35	Ionic pillars with pedestle and capital, etc., complete, 11′ diameter and 13″ high.	Each	..	16	..	..
36	Entablature with cornice freize, etc., complete ..	R. ft.	..	90	..	..
37	Balustrated parapet wall with intermediate masonry pillors, cornice, etc., complete top.	„	..	90	..	..
38	Stone carbels 5′=0 to 7′ and 2′ 6″x9″	Each	..	20	7	..
39	Drilling holes in walls for inserting stone carbels and fixing the same.	„	..	20	7	..
40	Kadapa slab flooring on 3″ concrete and cement pointing.	Sqr.	..	8·95	3·72	..
41	Finials over parapet wall pedastals similar to north side.	Each	..	16	..	..
42	Earth filling including carting, etc., complete ..	C. yd.	..	136	64	..
43	Converting the existing 3 windows into doors including polished Kadapa cills, complete painting, etc.	Each	..	..	..	..
44	Fixing three ventilators as per patern already putting at sides.	S. ft.	..	..	27	..
45	Clock with illuminated dial in pediment, etc,, complete.	L. S.	..	..	..	..
46	Sundry other unforeseen work such as adding old with new ones.	Do	..	..	..	..
47	Central ornamental masonry clock tower without clock.	Do	..	..	..	..
48	Cast iron figures of lions with lamp-post ..	Each	..	..	..	2
49	Drainage	L. S.	..	..	..	..
50	Burnt brick in chunam foundation and basement ..	C. ft.	3,222	2,871	1,664	3,239

GURU RAO SIRSI,
Assistant Engineer.

MISCELLANEOUS DEPARTMENTS.

MYSORE STATE TROOPS, BANGALORE.

Notice dated 24th February 1920.

1. Tenders are invited for the supply of the undermentioned articles required for the Military Stores, Mysore Government, Bangalore.

2. Tenders should be in the undermentioned form, sealed and addressed to the Chief Commandant, Mysore State Troops, and superscribed "Tenders for the supply of articles required for the Military Stores."

3. Tenders will be received at the Chief Commandant's Office, till 2 P.M., on Saturday the 20th March 1920, after which no tender will be received.

4. Tenders should clearly show the rate at which the article (which should correspond with the sealed sample) can be supplied. The sealed sample of the article could be seen in the Mysore Government Military Stores on any day during office hours.

5. Every tender should be accompanied with a deposit of Rs. 50 in currency notes. If the tender is accepted and the tenderer fails to undertake the contract, he will forfeit the amount. If the tender is not accepted, the amount will be returned to the tenderer.

6. The name of the successful tenderer will be notified in due course on the board at the Chief Commandant's Office and he will be required to deposit as security one-tenth of the value of the article to be supplied and to execute an agreement for the due fulfilment of the contract for the supply required.

7. Should the contractor fail to comply with any of the conditions detailed above, the contract will be forthwith cancelled, and the deposit credited to Government.

8. The Chief Commandant reserves to himself the right of accepting or rejecting any tender without assigning any reason therefor.

Articles required for the Mysore Military Stores.

Name of articles.	*Probable quantity.*
Blue serge for trousers	300 yards.
Silk sashes	25
Pagadi with lace pullows	25
Sowar and Barr khaki drill	10,000 yards.
New gram boilers capacity to boil 100 seers of gram made of iron plates, the thickness of the plate should be 1/16 inch at the top, 1/8 inch at the middle and 1/4 inch at the bottom. The boiler should have a top plate with hinges for closing and opening ...	9

B. CHAMARAJ URS, LT.-COL., *S. B.*,
Chief Commandant.